







HOBART

GENERAL LEGEND

AW	= drain water	KW	= cold water	üOKFF	= above finished floor
Dat	= dataline	KWw	= cold water soft	SFB	= separate filling-boiler
EZ	= power line (supply)	LR	= conduit Ø	VEW	= demineralized water
FD	= floor opening	CNS	= stainless steel (inox)	WD	= wall opening
HW-VL	= hot water flow	MK	= supply chanell	WS	= wall slot
HW-RL	= hot water return	PA	= equipotential conductor	WW	= warm water
KB	= cored hole Ø	STL	= control line	WWw	= warm water soft

HOBART



GENERAL INFORMATION



Connections: The connection of the convection steamer to all services (e.g. electrical, water, drain, exhaust) must comply with all national and local codes of practice and must be carried out by qualified people.

Dimensions: Dimensions in the drawing are finished dimensions in Millimeters.

Transport: Minimum measurements of entry doors = outer largest dimension of machine height + 300mm; machine width + 400mm!

Shut-off valves: The Shut-off valves for the convection steamer must be provided by the customer.

Floor drain: Splash floor drains should be installed for machine cleaning and for general cleaning purpose.

Ventilation: The ventilation and exhaust for the room must be according to VDI 2052. Radiated heat emissions must be considered.

Installation: Installation in accordance to DIN EN 61770.

Machine-Type: Convection steamer COMBI-mini					Heating: Electrical		
Model: HMJ 061 E					Operation: Right		
Capacity: 12 GN1/1		Inner Space: 78 dm³			Main-Switch: by others		
required supply (by others) (all installations according to local regulations) (technical feasibility must be checked on site)							
Electrical	Voltage	Frequency	Structure	Fuse	Total Load	Location	
3.7	PA	Equipotential				400mm AFFL	
3.0	EZ	400 V	50 Hz	3-N-PE	3 x 16 A	6,3 kW	400mm AFFL
Water	Consumption	Temp.	Chloride / Chlorine	Hardness	Conductance	Connection	Location
2.0	AW	Drain Approx. 80°C (Siphon provided by customer)				DN50	100mm AFFL
1.4	KW	min. 5l/min	max. 23°C	CL ⁻ max. 100mg/l	0-3,76°e	DN20	400mm AFFL
1.1	KWw			Cl ₂ max. 0,2mg/l	(0,5mmol/l)		
Water treatment: Generally we recommend the use of the demineralisation HYDROLINE STEAM CD at > 3°d							
Flow-Pressure provided <i>min. 1,5 bar / 21,7 psi - max. 6,0 bar / 87,0 psi</i> (above 6,0 bar must be lowered with a pressure reducer, below 1,5 bar need collulting with service)							
machine-side connentions and data							
WR = vapors exit / Location: upper edge machine					DA = Steam exit / Location: upper edge machine		
EZ = Power input / Location: lower edge machine		AW = Drain / Location: lower edge machine			KWw/KW / Location: lower edge machine		
Heat-Radiation (thermal output to the room)							
latent: 2.8 kW				sensibel: 1.8 kW			

-	-	-	-
Index	Änderungen / Changes	Datum / Date	Name

Das Urheberrecht an dieser Zeichnung verbleibt bei der HOBART GmbH.
Jede nicht von uns schriftlich genehmigte Benutzung, Verfielfältigung, Überlassung an Dritte ist strafbar und macht schadensersatzpflichtig.

This documnet contains proprietary and confidential data of HOBART GmbH. No disclosure, reproduction or use of any part there of may be made without written permission of HOBART GmbH.

HOBART

HOBART GmbH
Robert-Bosch-Straße 17
77656 Offenburg, Germany

Tel.: +49(0)781.600-0
Fax.: +49(0)781.600-2319
www.hobart.de

Datum / Date: 28.10.2019	Project:		
Gezeichnet / Drawn by: J.Boschert			
Geprüft / Checked by: -			
Projectmanager:	Maßstab / Scale: 1:20 @ A3	Order-No.:	Zeichnungsnummer / Drawing-No.:

